

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19714-00-00

Spot: NESESE

Sec/Twnshp/Rge: 32-22S-11E

990 feet from S Section Line,

330 feet from E Section Line

Lease Name: O'NEAL

Well #: 3

County: GREENWOOD

Total Vertical Depth: 1930 feet

Operator License No.: 33816

Op Name: CURRY, GREGG

Address: 1986 310TH ST

MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1930		75 SX
SURF	8	90		25 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/28/2017 8:00 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: JOE SAMUELS

Company:

Phone: (620) 437-2661

Proposed
Plugging
Method:

Proposed method of plugging is cement.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/28/2017 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1912', pumped 20 sxs cement, pulled tubing to 912', pumped 20 sxs cement, pulled tubing to 260', pumped 39 sxs cement, pulled tubing out topped well off w/5 sxs cement, casing shot @ 900' & 250', gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
JUL 10 2017
CHANUTE, KS


MH
INVOICED
AUG 2, 2017

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)



250 N. Water, Ste 200 - Wichita, KS 67202

HURRICANE SERVICES INC

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer:	CURRY OIL AND GAS			Customer Name:	GREG CURRY		Ticket No.:	50304	
Address:				Contractor:	H.S.I		Date:	6/28/2017	
City, State, Zip:				Job type:	PTA		Well Type:	OIL	
Service District:	MADISON, KANSAS			Well Details:	Sec		Temp:		Rt
Well name & No.:	ONEAL #3			Well Location:	MADISON	County:	GREENWOOD	State:	KANSAS
Equipment #	Driver	Equipment #	Driver	Equipment #	Driver	TRUCK CALLED			AM
201	KEVIN					ARRIVED AT JOB			PM
202						START OPERATION			AM
111						FINISH OPERATION			PM
30	JAKE					RELEASED			AM
						MILES FROM STATION TO WELL			10

ON LOCATION SAFETY MEETING. SPOT IN AND RIG UP. TUBING AT 1912' HOOK UP TO TUBING. BREAK CIRCULATION 5 BBL WATER. MIX AND PUMP 500# GEL. PUMP 5 BBL WATER, MIX AND PUMP 20 SX CEMENT DISPLACE 5 BBL WATER. TUBING AT 912' BREAK CIRCULATION. MIX AND PUMP 500# GEL, PUMP 2 BBL WATER, MIX AND PUMP 20 SX CEMENT DISPLACE 1 BBL. TUBING AT 280'. BREAK CIRCULATION. MIX AND PUMP 39 SACKS CEMENT. PULL TUBING TOP OFF AND SQUEEZE SURFACE WITH 5 SX CEMENT.

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Net Amount
C001	Heavy Equip. One Way	mi	10.00	\$3.25	\$32.50	\$27.63
C002	Light Equip. One Way	mi	10.00	\$1.50	\$15.00	\$12.75
C004	Minimum Ton Mile Charge	job	1.00	\$300.00	\$300.00	\$255.00
C020	Cement Pump	each	1.00	\$675.00	\$675.00	\$573.75
CP009	60/40 Pozmix Cement	sack	84.00	\$12.85	\$1,079.40	\$917.49
CP013	Bentonite Gel	lb	289.00	\$0.30	\$86.70	\$73.70
CP013	Bentonite Gel	lb	500.00	\$0.30	\$150.00	\$127.50
T003	Vacuum Truck 80 bbl	hr	2.00	\$84.00	\$168.00	\$142.80
T012	Backhoe	hr	1.00	\$75.00	\$75.00	\$63.75
T014	Welder + mileage one way	hr	1.00	\$65.00	\$65.00	\$55.25

TERMS: Cash in advance unless Hurricane Services Inc (HSI) has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/4% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to effect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and subject to collection. Prices quoted are estimates only and are good for 30 days from the date of issue. Pricing does not include federal, state, or local taxes, or royalties and stated price adjustments. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services. Discount rate is based on 30 days net payment terms or cash.

DISCLAIMER NOTICE:
This technical data is presented in good faith but no warranty is given by and HSI assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or service. The information presented is HSI best estimate of the actual results that may be achieved and should be used for comparison purposes and make no guarantee of future production performance. Customer warrants that well and all associated equipment in acceptable condition to receive services by HSI. Likewise, the customer will guarantee proper operational care of all customer owned production and associated equipment, while HSI is on location performing services which could adversely affect the performance of such services. Authorization below acknowledges receipt and acceptance of all terms and conditions stated above.

X _____
CUSTOMER AUTHORIZED AGENT

Gross: \$ 2,646.60		Net: \$ 2,249.61
Total Taxable	\$ -	Tax Rate:
Free and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		Sale Tax: \$ -
Total: \$ 2,249.61		
Date of Service:	6/28/2017	
HSI Representative:	JAKE HEARD	
Customer Comments:		