

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21040-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 20-11S-18W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WASINGER Well #: 1
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 9346
Op Name: DIEHL OIL INC
Address: 205 E 13TH PO BOX 234
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3499		150 SX
SURF	8.625	210		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2017 1:30 PM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: GLENN D DIEHL Company: DIEHL OIL INC Phone: (785) 625-6711

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # hulls and 12 sx gel.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2017 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3109' and pumped 6 sx gel followed by 75 sx cement w/150 # hulls. Pulled tubing to 1816' and pumped 150 sx cement w/250 # hulls. Pulled tubing to 500' and pumped 50 sx cement. Circulated cement to the pit. POOH. Topped off w/10 sx cement. Casing stayed full. Hooked to braden head and pressured to 350 psi. No fluid was moved. Total of 285 sx cement, 6 sx gel and 400 # hulls were used to plug.

GPS: 39.08757 -099.34141

Perfs:

Top	Bot	Thru	Comments
3481	3486		
3346	3348		
3338	3340		
3325	3327		
3207	3209		
3170	3172		
3147	3149		
1230			

Remarks: GLOBAL CEMENTING TICKET # 2950

Plugged through: TBG

INVOICED
AUG 8 2 2017

District: 04

Signed Ray A Dinkel

KCC WICHITA

(TECHNICIAN)

CM

JUN 13 2017

JUL 20 2017

RECEIVED