

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-20156-00-01
Spot: SWNW Sec/Twnshp/Rge: 19-24S-15W
3206 feet from S Section Line, 4551 feet from E Section Line
Lease Name: YOUNG OWWO Well #: 1
County: STAFFORD Total Vertical Depth: 4384 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4230		WITH 2 SX CMT
CIBP		4337		
PROD	4.5	4381	0	WITH 150 SX CMT
SURF	8.625	208		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/06/2017 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: ROB LONG Company: FG HOLL Phone: (620) 793-0915

Proposed Plugging Method: SET CIBP @ 4230' WITH 2 SX CMT. PERFORATE AT 1050' WITH 10 SX GEL & 50 SX CMT. PERFORATE AT 250' WITH CMT TO 0'.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2017 8:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

7/6/17: SET CIBP @ 4230' & TOPPED WITH 2 SX CMT. PRESSURE TEST CASING TO 300 PSI. PERFORATE 2 SHOTS/FT AT 1050' & 250'. SHUT DOWN. 7/10/17: TIH WITH 2 7/8" TBG TO 1050' & ESTABLISH CIRCULATION WITH FRESH WATER. PUMP 10 SX GEL FOLLOWED BY 50 SX CMT WITH 200# HULLS IN LAST 25 SX CMT. PULL TBG TO 250' & ESTABLISH CIRCULATION WITH FRESH WATER. PUMP 75 SX CMT TO FILL 4 1/2" CASING. PUMP 110 SX CMT TO FILL ANNULUS TO SURFACE. 7/11/17: CMT FELL 8' IN 4 1/2" CASING & 12' IN ANNULUS. DRY CMT WAS USED TO FILL TO 5' BELOW GROUND LEVEL.

Top	Bot	Thru	Comments
4286	4304		

INVOICED
AUG 29 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed

Ken Scofield
JA (TECHNICIAN)

RECEIVED
JUL 17 2017
KCC DODGE CITY