

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21292-00-00
Spot: SENWSE Sec/Twnshp/Rge: 31-9S-17W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GANOUNG Well #: 3
County: ROOKS Total Vertical Depth: 3650 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3650		200 SX
SURF	8.625	165		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2017 8:30 AM
Plug Co. License No.: 35046 Plug Co. Name: RED LINE WELL SERVICE, LLC
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Two staged using DV Tool at 1450' w/425 sx cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2017 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 2019' and pumped 90 sx cement w/250 # hulls. Circulated cement to pit. POOH. Hooked to casing and pumped 30 sx cement pressured to 350 psi. Casing hanger cut off 8 5/8" surface casing orange peeled to 4 1/2" casing. Pressured up to 300 psi with no fluid moved.

GPS: 39.22433 -099.25795

Perfs:

Top	Bot	Thru	Comments
3554	3557		
3487	3490		
3446	3451		
3428	3432		
3322	3325		

Remarks: SWIFT WELL SERVICES TICKET # 30019

Plugged through: TBG

District: 04

KCC WICHITA Signed Ray A. Dinkel (TECHNICIAN) CM
JUL 20 2017
RECEIVED

INVOICED
AUG 29 2017

JUN 13 2017