

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21191-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 31-9S-17W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GANOUNG Well #: 1  
County: ROOKS Total Vertical Depth: 3610 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3609		200 SX
SURF	8.625	168		110 SX
T1	2.375	3603		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2017 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/1000 # hulls.  
Squeezed at 940' w/290 sx cement.  
Casing leaks cedar hills and 2400' - 2500'.  
Production perforations: 3251' - 3566'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/07/2017 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' and pumped 125 sx cement w/500 # hulls. Pulled tubing to 2114' and pumped 100 sx cement w/500 # hulls. Pulled tubing to 1053' and pumped 75 sx cement. Circulated cement to surface. Topped off 4 1/2" casing with 65 sx cement. Hooked to 8 5/8" x 4 1/2' annulus and pumped 10 sx cement.

GPS: 39.22599N -099.25459W

Perfs:

Top	Bot	Thru	Comments
3564	3566		
3562	3566		
3531	3542		
3521	3525		
3492	3495		
3473	3475		
3452	3457		
3437	3440		
3374	3376		
3307	3311		
3251	3254		

Remarks: SWIFT SERVICES TICKET # 30045

Plugged through: TBG

District: 04

KCC WICHITA Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUN 16 2017

INVOICED  
AUG 29 2017