

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-20864-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 19-14S-27W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: JACOBS A Well #: 1  
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 5107  
Op Name: H-30, INC.  
Address: 251 N. WATER, STE 10  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4375		135 sx
SURF	8.625	218		145 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2017 9:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JEFFREY A. BURKE Company: H-30, INC. Phone: (316) 250-5655

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # hulls and 13 sx gel.  
DV Tool at 2000' w/335 sx cement.  
Perforations: 3932' - 3968'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/20/2017 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3906' and pumped 13 sx gel followed by 65 sx cement w/300 # hulls. Pulled tubing to 2341' and pumped 250 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 38.81772 -100.37208


Perfs:

Remarks: QUALITY CEMENT TICKET # 1570

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUN 26 2017

Form CP-2/3

INVOICED  
AUG 29 2017