

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21496-00-01
Spot: SWSNWSW Sec/Twnshp/Rge: 28-33S-13E
1604 feet from S Section Line, 4476 feet from E Section Line
Lease Name: SWANEY Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 700 feet

Operator License No.: 33712
Op Name: CLARK ENERGY, LLC
Address: 1198 RD 31
HAVANA, KS 67347

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	700		85 SX
SURF	7	150		43 SX

Well Type: SWD UIC Docket No: D25892.0 Date/Time to Plug: 10/16/2017 12:00 AM
Plug Co. License No.: 31696 Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP
Proposal Revd. from: BUDDY FINNEY Company: Phone: (620) 505-0479

Proposed Plugging Method: Gel hole at TD, pump 5 sacks of cement at TD, pull tubing up to 500 feet and pump 5 sacks of cement, pull tubing to 275 feet and circulate cement to surface. Pull tubing out of hole and top off with cement.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2017 11:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 607' gelled hole and spotted 4 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 2" and topped well off. A total of 22 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
640	660		

RECEIVED
KCC DIST # 3
OCT 31 2017
CHANUTE, KS

DS

INVOICED
NOV - 6 2017

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)