

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04617-00-01
Spot: SWSENE SW Sec/Twnshp/Rge: 9-19S-12W
1648 feet from S Section Line, 3083 feet from E Section Line
Lease Name: KNOP Well #: 6
County: BARTON Total Vertical Depth: 3171 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3427		150 SX
SURF	8.625	156		175 SX

Well Type: EOR UIC Docket No: E16524.6 Date/Time to Plug: 09/27/2017 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: K & N PETROLEUM, INC. Phone: (620) 793-6005

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 400 # hulls and 12 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 680' and 150'. Ran tubing to 3100' and pumped 12 sx gel w/200 # hulls followed by 50 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 70 sx cement. Pulled tubing to 700'. Circulated cement to surface on casing with 115 sx cement. Closed valve on casing. Circulated cement to surface on surface pipe with 50 sx cement. Pulled tubing and topped off with 10 sx cement.

GPS: 38.41012 -098.65617

Perfs:

Top	Bot	Thru	Comments
3329	3333		
3194	3200		
3153	3158		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

INVOICED
NOV - 9 2017

District: 04

Signed Bruce Rodie
(TECHNICIAN) *cm*

OCT 05 2017

KCC WICHITA CP-2/3
OCT 17 2017
RECEIVED