

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-23266-00-01  
Spot: NWSWNE Sec/Twnshp/Rge: 5-34S-13E  
3587 feet from S Section Line, 2390 feet from E Section Line  
Lease Name: KIRKPATRICK A L Well #: 10  
County: CHAUTAUQUA Total Vertical Depth: 1214 feet

Operator License No.: 33252  
Op Name: MATADOR, INC.  
Address: PO BOX 337  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1214		
SURF	7	40		

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: TIM D. NORDELL Company: \_\_\_\_\_ Phone: (620) 725-3366

Proposed Plugging Method: RUN 1" TO TD, GEL HOLE, SPOT 5 SX CMT @ PERFS. PULL UP TO 700' SPOT 5 SX CMT. PULL UP TO 275' CMT TO SURF.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 08/14/2017 12:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 1000' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 40 sacks of cement were used to plug this well. Well was cut off and location restored.

**Perfs:**

Top	Bot	Thru	Comments
1013	1020		

RECEIVED  
KCC DIST # 3  
OCT 17 2017  
CHANUTE, KS  
DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT TO OPERATOR BY THE KCC. OPERATOR HAD LOST LEASE ON PROPERTY.

Plugged through: TBG

INVOICED  
NOV - 9 2017

District: 03

Signed *D. Sims*  
(TECHNICIAN)