

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-21016-00-01  
Spot: W2E2E2NW Sec/Twnshp/Rge: 6-10S-24W  
3960 feet from S Section Line, 3080 feet from E Section Line  
Lease Name: RIEDEL Well #: 5  
County: GRAHAM Total Vertical Depth: 4048 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4057		175 SX
SURF	8.625	215		175 SX

Well Type: EOR UIC Docket No: E25015.2 Date/Time to Plug: 10/23/2017 8:30 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perforations: 3858' - 3862' and 3983' - 3988'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/23/2017 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2160' and 210'. Ran tubing to 3648' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2815' and pumped 100 sx cement. Pulled tubing to 1806' and pumped 185 sx cement. Good circulation of cement out of casing and backside. Pulled tubing out. Topped off casing with 20 sx cement.

Perfs:

Top	Bot	Thru	Comments
3983	3988		
3858	3862		


GPS: 39.21530 -100.04465

Remarks: HURRICANE SERVICES TICKET #100819

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

(M)

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 24 2017

INVOICED  
NOV - 8 2017