

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24236-00-01  
Spot: NWSWSENE Sec/Twnshp/Rge: 11-19S-12W  
2988 feet from S Section Line, 1109 feet from E Section Line  
Lease Name: WEISS Well #: 2  
County: BARTON Total Vertical Depth: 3606 feet

Operator License No.: 31085  
Op Name: PAUL'S OILFIELD SERVICE  
Address: PO BOX 1773  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3528		125 SX
SURF	8.625	253		150 SX

Well Type: SWD UIC Docket No: D26542.0 Date/Time to Plug: 10/10/2017 12:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: PAUL WERTH Company: PAUL'S OILFIELD SERVICE DBA Phone: (620) 793-2585

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement and 500 # hulls.  
Casing parted in well at 1500'. Tried to get past where casing was parted and could not. Will plug from there. Operator has squeezed at 1100' and 1400' w/275 sx cement. Circulated cement up the backside. Will not perforate well.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/10/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 1364' and pumped 65 sx cement. Pulled tubing to 700' and pumped 40 sx cement. Pulled tubing to 300'. Circulated cement to surface with 40 sx cement. Pulled tubing. Topped off with 5 sx cement. Tied to surface pipe and cement pushed up around the surface pipe.

GPS: 38.41389 -098.612330

Remarks: SWIFT CEMENTING TICKET # 30499

Plugged through: TBG

INVOICE  
ADP - 8 2017

District: 04

Signed

*Bruce Rodie*

KCC WICHITA

(TECHNICIAN)

CM

OCT 30 2017

OCT 19 2017

RECEIVED