

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-22035-00-01  
Spot: S2NENWNW Sec/Twnshp/Rge: 35-8S-22W  
4945 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BUSS OWWO Well #: 2  
County: GRAHAM Total Vertical Depth: 3920 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1760		360 SX
SURF	8.625	367		250 SX

Well Type: SWD UIC Docket No: E26184.0 Date/Time to Plug: 10/18/2017 1:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
8 5/8" surface casing set at 367' w/250 sx cement.  
4 1/2" production casing set at 1760' w/360 sx cement. Cement did not circulate. Ran 3/4" pipe to 370' and pumped 90 sx cement. Cement circulated to surface.  
TD 3920'. PBTD 1556'.  
Perforations: 1422' - 1472'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/19/2017 3:40 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 4 1/2" production casing and pumped 40 sx cement without hulls and 60 sx cement w/250 # hulls. Pressured to 1000 psi. 8 5/8" surface casing is full of cement.  
GPS: 39.32042N -099.74992W

Perfs:

Top	Bot	Thru	Comments
1422	1472		

Remarks: GLOBAL OILFIELD SERVICES LLC TICKET # 3103

Plugged through: CSG

District: 04

Signed Darrel Dipman  
KCC WICHITA (TECHNICIAN)

OCT 23 2017

OCT 30 2017

RECEIVED

Form CP-2/3

INVOICED