

1 080378

15.185.11636.0001
DOCKET NO. D-17,837

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

NE NW SE, SEC. 34, T 21 S, R 13 (W) X

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name R.C. Gates SWD Well # 8

Operator: Mobil Oil Corporation

County Stafford 133.38

Name & Address P. O. Box 5444

Well Total Depth 4104 feet

Denver, CO 80217-5444

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 276

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P. O. Box 5444, Denver, CO 80217-5444

Company to plug at: Hour: 9:30 am Day: 15 Month: May Year: 19 85

Plugging proposal received from Jay Chase

(company name) Mobil (phone) 303-298-2696

were: 5 1/2" at 3719' 4 1/2" liner from 3377-3984', Open hole from 3719-4104', Perfs from 3620-38, 3533-37, 3514-19, 3392-96', 2 3/8" packer & tubing stuck at 3328', parted at 800'. No bottom plug - could not get to bottom with any type of tool.

Pumped 50 sx cement through 2 1/2" tubing at 732'. Waited 3 hours and tagged bottom with tubing. Cement at 609', pumped 75 sx cement at 587. Broke circulation. Pumped

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 am Day: 16 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 150 sx cement at 150'. Pumped 25 sx cement at 30'. Well on slight vacuum.

RECEIVED STATE CORPORATION COMMISSION

5-16-85 - tagged cement at 140'. Circulated 65 sx cement to surface. Cement held

MAY 28 1985 5-28-85

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 50/50 Pozmix 2% gel. by Halliburton. Recovered 457' 5 1/2" casing (casing parted at 457') (If additional description is necessary, use BACK of this form.)

INVOICED

DATE: 6-6-85

Signed J. H. Metz (TECHNICIAN)

INV. NO. 8380

JUN 25 1985