

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20971-00-00  
Spot: CS2S2NW Sec/Twnshp/Rge: 34-21S-13W  
2310 feet from N Section Line, 1320 feet from W Section Line  
Lease/Unit Name: MCCOY Well Number: 1  
County: STAFFORD Total Vertical Depth: 3748 feet

Operator License No.: 33069  
Op Name: ENCORE OPERATING COMPANY  
Address: 1601 BLAKE STREET, SUITE 500  
DENVER, CO 80202

Production Casing Size: 4.5 feet: 3622 WITH 250 SX CMT  
Surface Casing Size: 8.625 feet: 283 WITH 175 SX CMT  
\$/21.81

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2003 9:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: PUMP 5 SX CMT 50' ABOVE PERFS. PUMP 50 SX CMT AT 750'. PUMP 50 SX CMT AT 310'. PUMP 10 SX CMT AT 40'.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/07/2003 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 3573'. PERFS AT 3422-26, 3449-53, & 3524-28'. CASING PULLED INTO AT 300', SEVERELY CORRODED. SANDED BACK TO 3371' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PERFORATED 4 1/2" CASING @ 750'. RUN 2 3/8" TUBING INTO 715'. 1ST PLUG AT 715' WITH 10 SX GEL & 50 SX CMT. PULLED TUBING OUT OF HOLE. LET CMT SET. TAG CMT AT 315'. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
MAR 18 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL W/3% CC BY ALLIED. RECOVERED 300' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED

DATE 3-18-03

WV. NO. 2003061310

Form CB-20