

To: 1 052120
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-21,337.0000
SE NE SE, SEC. 34, T 21 S, R 13
1650 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8653
Operator: Petroleum Technologies, Inc.
Name
Address 500 Nichols Rd., Ste. 407
Kansas City, MO 64112

Lease Name Hooper Well # 1
County Stafford 119.67
Well Total Depth 3682 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor D S & W Well Service, Inc. License Number 6901
Address 403 W. Front, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 2 Month: 4 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D S & W Well Service, Inc. (phone) 316-587-3361

logs: 5 1/2" at 3681' w/165 sx cement, Perfs at 3513-17, 3450-54, 3364-70, 3394-3400', Open hole 3681-82'
1st plug sand back to 3310' and dump .5 sx cement on top of sand through bailer
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11 a.m. Day: 2 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3310' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1750' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 4-10-97
INV. NO. 47904

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED
KANSAS CORP COM
APR - 3 A 10:40