

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23100-00-00
Spot: SESWNW Sec/Twnshp/Rge: 16-21S-13W
2310 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: JANE Well Number: 1
County: STAFFORD Total Vertical Depth: 3750 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

Production Casing Size: 5.5 feet: 3749 175 SX CMT
Surface Casing Size: 8.625 feet: 390 250 SX CMT

\$ 121⁸⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2003 2:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed
Plugging
Method:

SAND OFF TO 3600' & 5 SX CMT. 50 SX CMT AT 750'. 50 SX CMT AT 425'. 10 SX CMT AT 40'.

Plugging Proposal Received By: JIM HOLLAND

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/01/2003 3:00 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PERFS AT 3668-88'. SAND BACK TO 3600' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 425' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
OCT 14 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2630' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 10-14-03

REF. NO. 2004060622

Form CP-2/3