

To: 1-060123 3-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-21,078.0000 6 of

SE NE SE, SEC. 1, T. 21 S, R. 34 W/E
1650 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7344
Operator: Clyde M. Becker
Name & Address: 212 First National Bldg.
Ponca City, OK 74601

Lease Name Buerkle Well # 1
County Finney 158.27
Well Total Depth 4870 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 3 5/8 feet 228

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling Company License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 6 p.m. Day: 2 Month: 3 Year: 19 92

Plugging proposal received from Duane Bell

(company name) Cheyenne Drilling Company (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2020-2110'

1st plug at Hugoton/Council Grove with 100 sx cement,

2nd plug at 2150' with 50 sx cement, 3rd plug at 1250' with 50 sx cement,

4th plug at 700' with 50 sx cement, 5th plug at 260' with 50 sx cement,

6th plug at 40' with 10 sx cement, 7th plug to circulate rathole with 15 sx cement,

8th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 p.m. Day: 2 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 3027' with 100 sx cement;

2nd plug at 2160' with 50 sx cement, 3rd plug at 1263' with 50 sx cement,

4th plug at 706' with 50 sx cement, 5th plug at 279' with 50 sx cement,

6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement,

8th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Dowell.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (X) / did not observe this plugging.

DATE 4-7-92

Signed _____ (TECHNICIAN)

INV. NO. 34875

3-2

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1992
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 2-3-92

State of Kansas
NOTICE OF INTENTION TO DRILL 055-21,078

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT #
SEAT Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date February 15, 1992
month day year

Spot SE NE SE Sec 1 Top 21 S. Rg 34 East West

OPERATOR: License # 07344
Name: Clyde M. Becker
Address: 212 First National Bldg.
City/State/Zip: Ponca City, OK 74601
Contact Person: Clyde M. Becker
Phone: 405-765-8788

1650 feet from South / North line of Section,
330 feet from East / West line of Section,
IS SECTION REGULAR IRREGULAR

CONTRACTOR: License #: 5382
Name: Cheyenne Drilling Co.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Finney
Lease Name: Buerkle Well #: 1
Field Name: UNNAMED

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext. Air Rotary
GWVO Disposal Wildcat Cable
Seismic: # of Holes Other

Is this a Prorated/Spaced Field? yes no
Target Formation(s): St. Louis
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2931 feet MSL

If GWVO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water well within one-quarter mile: yes no
Public water supply well within one mile: yes no
Depth to bottom of fresh water: 150
Depth to bottom of usable water: 1150
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 225
Length of Conductor pipe required:

Directional, Deviated or Horizontal wellbore? yes no
If yes, true vertical depth:
Bottom Hole Location:

Projected Total Depth: 4850
Formation at Total Depth: St. Louis
Water Source for Drilling Operations:
well farm pond other

DWR Permit #:
Will Cores Be Taken? yes no
If yes, proposed zone:
200' Alt. II Req.

Exp. 7/29/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Duane Bell
SPUD DATE 2-23-92 INIT. DG
LENGTH SURFACE PLANNED 227'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 228' CONDUCTOR
ANHYDRITE T-2022 B-2#1D ELEVATION
TD 4870 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
1 Hug./Council @ 3027 Ft. W/ 100 SX
2 Anhydrite Base @ 2150 Ft. W/ 50 SX
3 1/2 Base Anyh. @ 1250 Ft. W/ 50 SX
4 1/2, 1/2 Plug @ 700 Ft. W/ 50 SX
5 Bottom Surface @ 260 Ft. W/ 50 SX
6 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling
TECHNICIAN CM DATE 3-6-92
TYPE OF CEMENT 60/40 27
STARTING TIME 6: (AM/PM) DATE
COMPLETION TIME 9:30 (AM/PM) DATE
CEMENT COMPANY Dowell

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1992

CONSERVATION DIVISION
Wichita, Kansas