

11-2
API NUMBER 15-093-21,122-0000

SE NW, SEC. 4, T 21 S, R 35 W/E

3300 feet from S section line

3300 feet from E section line

Lease Name Klein Well # 1

County Kearny 164.12

Well Total Depth 5050 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 2 Month: 11 Year: 19 90

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2241-67'

1st plug at 2260' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 240' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:15 p.m. Day: 2 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 240' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 11-19-90

INV. NO. 30002

11-2

EFFECTIVE DATE: 10-16-90

15.093-21122-0000

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL 093-21,122

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 30 90
month day year

SE NW Sec 4 Twp 21S S, Rg 35 East West

OPERATOR: License # 5422
Name: Abercrombie Drilling, Inc.
Address: 150 N. Main, Suite 801
City/State/Zip: Wichita, KS 67202
Contact Person: Jerry A. Langrehr
Phone: 316-262-1841

3300 feet from South line of Section
3300 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5422
Name: Abercrombie Drilling, Inc.

County: Kearny
Lease Name: Klein Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:

X Oil Inj Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
GWD Disposal X Wildcat Cable
Seismic; # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): Marm
Nearest lease or unit boundary: 660'
Ground Surface Elevation: NA feet MSL

If GWD: old well information as follows:

Operator: N/A
Well Name:
Comp. Date: Old Total Depth:

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 120'
Depth to bottom of usable water: 1050'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: None
Projected Total Depth: 5000'
Formation at Total Depth: Miss
Water Source for Drilling Operations:
well farm pond X other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: N/A

DWR Permit #: will file
Will Cores Be Taken? yes X no
If yes, proposed zone: N/A

Exp. 4/11/91

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

SACK Per High

Pusher Bill Gray
SPUD DATE 10/20/90 INIT. SD
LENGTH SURFACE PLANNED 200

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 216 CONDUCTOR
ANHYDRITE T-22-11 B-67 ELEVATION

TD 5050 FORMATION

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 2260 Ft. W/ 50 SX

1/2 Base Anhyd. @ 1300 Ft. W/ 80 SX

1/2 Plug @ Ft. W/ 95 SX

Bottom Surface @ 240 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond
Hauling

TECHNICIAN DR DATE 10-30-90

TYPE OF CEMENT 40-40-670 4" / 6" 5" 2

STARTING TIME 11:00 (AM/PM) DATE 11-2-90

COMPLETION TIME 5:15 (AM/PM) DATE 11-2-90

CEMENT COMPANY B.S.