

1 100076

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-093-20,647.0000

C NE NW, SEC. 4, T 21 S, R 35 (W/E)

4620 feet from N/S section line

3300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Klein Well # 1

Operator: J. A. Allison

County Kearny 151.61

Name & Address 300 W. Douglas, Suite 305

Well Total Depth 4665 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5:00 pm Day: 9 Month: October Year: 19 85

Plugging proposal received from Ronnie Hoover

(company name) Kelso (phone) 316-938-2941

were: 5 1/2" at 4664' Perfs at 2720-26'; 2726-28'; 4489-02', 4502-08'; 4513-17'; 4554-58';
4590-96'

1st plug pump 220 sx cement and stop plug at 2670'

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pump 200 sx cement

Orders given by Steve Durrant

Plugging Proposal Received by Phyllis Lindsey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00 pm Day: 9 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 220 sx cement and pushed plug to 2730',

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped 200 sx cement.

Maximum pressure 300 psi and shut in 50 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1985
10-15-85

INVOICED

DATE OCT 17 1985

INV. NO. 10636

Signed Phyllis Lindsey
(TECHNICIAN)