

To: 1 051803 4-22
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-093-21,283.0000

NE NE NE, SEC. 4, T 21 S, R 35 W
440 feet from NW section 11
440 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name:
Address Rt. 1, Box 56
Great Bend, KS 67530

Lease Name Klein "B" Well # 1
County Kearny
Well Total Depth 5046 163.99 ft.
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied License Number _____
Address _____

Company to plug at: Hour: 10 a.m. Day: 22 Month: 4 Year: 19 94

Plugging proposal received from Mr. Dipman
(company name) Abercrombie (phone) 316-793-8186

logs: 4 1/2" at 4915' w/225 sx cement, PBD 4870', Perfs at 4616-19, 4719-21'
DV at 1362' w/225 sx cement

1st plug fill 4 1/2" with 300 lbs. hulls and 250 sx cement,

2nd plug pump 150 sx cement down annulus.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 22 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 300 lbs. hulls and 250 sx cement.

Maximum pressure 800 psi and shut in 600 psi.

2nd plug pumped down 8 5/8" X 4 1/2" annulus with 20 sx cement.

Maximum pressure 600 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1994

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

(if additional description is necessary, use BACK of this report)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 4-29-94

Signed Richard W. Lacy
TECHNICIAN

INV. NO. 40361

4-22