

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20256-00-00  
Spot: CNW Sec/Twnshp/Rge: 15-21S-34W  
1320 feet from N Section Line, 3960 feet from E Section Line  
Lease/Unit Name: VAUGHAN Well Number: 1  
County: FINNEY Total Vertical Depth: 3080 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN, LLC  
Address: 3200 FIRST PLACE TOWER  
TULSA, OK 74103

Conductor Pipe: Size feet: 8/100.10  
Surface Casing: Size 8.625 feet: 501 WITH 350 SX CMT  
Production: Size 4.5 feet: 3014 WITH 200 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/21/2001 9:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 20 SX CMT & HULLS ON BOTTOM. 1ST PLUG AT 1100' WITH 80 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 12/21/2001 5:00 PM

WitnessType: Plugging Operations Were Not Witnessed  
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 200# HULLS & 20 SX CMT. PRESSURED UP TO 600#. SHOT CASING AT 1130'. 1ST PLUG PULLED UP TO 1100'. CIRCULATED HOLE WITH MUD. PUMPED 80 SX CMT AT 1100'. 2ND PLUG PULLED UP TO 550' & PUMPED 50 SX CMT. 3RD PLUG PULLED UP TO 40' & PUMPED 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1130' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
KANSAS CORPORATION COMMISSION

Signed

Richard W. Lacey

(TECHNICIAN)

JAN 07 2002

CONSERVATION DIVISION

DEC 28 2001 INVOICES

DATE 01-08-02

INV. NO. 2002061215