

1 020770

6-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-21,237-0000
C SE NE, SEC. 15, T 21 S, R 34 W/8
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652
Operator: Mustang Oil & Gas Corporation
Name & Address 100 S. Main, Ste. 300
Wichita, KS 67202

Lease Name Schmitz Well # 1-15
County Finney
Well Total Depth 4840 157.30 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mustang Oil & Gas Corp. License Number 5652
Address 100 S. Main, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 1 Month: 6 Year: 1994
Plugging proposal received from Al Hammersmith
(company name) Mustang Oil & Gas Corp. (phone) 316-792-7323

Logs: 4 1/2" at 4839' w/150 sx cement, PBTDS:4807', Perfs at 4705-16'
1st plug sand back to 4650' and dump 4 sx cement on top of sand through bailer,
2nd plug at 2800' with 25 sx cement, 3rd plug at 1150' with 80 sx cement,
4th plug at 600' with 30 sx cement, 5th plug at 330' with 50 sx cement,
6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3 p.m. Day: 1 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4655' and dumped 4 sx cement on top,
2nd plug pumped 50 sx cement at 2608', mud between all plugs,
3rd plug at 1100' with 80 sx cement,
4th plug at 600' with 30 sx cement,
5th plug at 330' with 50 sx cement,
6th plug at 40 to -4' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2608' of 4 1/2" casing. Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED (STAMP) observe this plugging.

DATE 6-20-94
INV. NO. 40589

Signed Glean R. Barlow
(TECHNICIAN)