

1050959

11-14-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-20,754.0000

C SW NW, SEC. 10, T 21 S, R 34 (W)

3300 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Davis Well # G#1

Operator: American Energies Corporation

County Finney 157.95

Name & Address 155 North Market, Suite 710

Well Total Depth 4860 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Company License Number 5886

Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 12:30 a.m. Day: 14 Month: 11 Year: 19 87

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Company (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2088-2106'

1st plug at 3000' with 100 sx cement, 2nd plug at 2100' with 50 sx cement,

3rd plug at 1300' with 80 sx cement, 4th plug at 360' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 14 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

2nd plug at 2100' with 50 sx cement,

3rd plug at 1300' with 80 sx cement,

4th plug at 360' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx

Remarks: Used 60/40 Pozmix 6% gel by Allied. cement.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 12-2-87

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 19013

11-14

RECEIVED STATE CORPORATION COMMISSION

11-18-87 NOV 18 1987

CONSERVATION DIVISION Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date November 3, 1987 month day year

API Number 15-055-20,754 2

OPERATOR: License # 5399 American Energies Corporation 155 North Market, Suite 710 Wichita, Kansas 67202 Alan L. DeGood 263-5785

C SW NW Sec. 10 Twp. 21 S, Rg. 24 X West 3300 Ft. from South Line of Section 4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5886 Warrior Drilling Co. Wichita, Kansas

Nearest lease or unit boundary line 660 feet County Finney Lease Name DAVIS Well # "G" #1 Ground surface elevation N/A est. 2980 feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 260' Depth to bottom of usable water 1300' Surface pipe by Alternate 1-2 X Surface pipe planned to be set 320' Conductor pipe required Projected Total Depth 4900' Formation Mississippian

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 10/28/87 Signature of Operator or Agent Alan L. DeGood Tide Vice-President

For KCC Use: Conductor Pipe Required feet Minimum Surface Pipe Required 260 feet per Alt. This Authorization Expires 4-28-88 Approved By R.H. 10-28-87

EFFECTIVE DATE: 11-2-87

Spud 11-4/87 Set - 320

Sec. Twp. S, Rg. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2000' feet depth with 30 sxs of Lite
2nd plug @ 1300' feet depth with 40 sxs of Lite
3rd plug @ 320' feet depth with 50 sxs of Lite
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 10 sxs (b) Mousehole with 5 sxs

PUSHER Warren Bennis TD 4860 FORMATION MISS SURFACE PIPE 8 7/8 @ 334 ANHYDRITE 2055-268 ELEVATION STARTING TIME & DATE 2:50 AM 11-14-87 COMPLETION TIME & DATE 4:30 AM 11-14-87 1st PLUG @ 3000 FT. WI 100 SX 2nd PLUG @ 2100 FT. WI 50 SX 3rd PLUG @ 1300 FT. WI 80 SX 4th PLUG @ 360 FT. WI 40 SX 40 RAT HOLE CIRCULATED WI 15 SX MOUSE HOLE CIRCULATED WI 10 SX WATER WELL PLUGGED WI CEMENT COMPANY ALLCIEB

TECHNICIAN 60/40 @ 9/6 gel

RECEIVED DATE CORPORATION COMMISSION NOV 18 1987 CONSERVATION DIVISION Wichita, Kansas