

To: 1 080150 10-10
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-055-20,622.0000
C SW SW, SEC. 10, T 21 S, R 34 W/E
660 feet from S section line
4620 feet from E section line
Jessen A
Lease Name _____ Well # 1

TECHNICIAN'S PLUGGING REPORT
Operator License # 31458

Operator: H J Inc. d.b.a. Herman Lang Oil & Gas
Name & Address 70 N. Farmland Rd.
Garden City, KS 67846

County Finney 159.25
Well Total Depth 4900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well Gas Well _____ Input Well _____ SKD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mikes Testing & Salvage Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 9 a.m. Day: 10 Month: 10 Year: 19 97

Plugging proposal received from Kenneth Lang

(company name) H J Inc. (phone) 316-276-3442

logs: 4 1/2" at 4900' w/375 sx cement, DV at 1926' with 250 sx cement, Perfs at 4792-95'

1st plug pump 25 sx cement with 100 lbs. hulls mixed in at 4680'

2nd plug pull tubing to 2600' and pump 100 lbs. hulls and 20 sx cement.

3rd plug pull tubing to 1900' and circulate cement to surface.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 10 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT Ran 2 3/8" tubing to 4680' and pumped 100 lbs. hulls and 25 sx cement,
pulled tubing to 2600' (had holes in casing from 2300-2600'). Pumped 100 lbs. hulls and 20 sx
cement. Pulled tubing to 1900' and circulated cement to surface with 130 sx. Pulled tubing to
450' and pumped 40 sx cement, circulated. Pulled tubing, topped off with 35 sx cement.

Still dropping. Pressured up 8 5/8" X 4 1/2" to 500 psi.

10-16-97 RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

INVOICED (If additional description is necessary, use BACK of this invoice)
OCT 16 1997
CONSERVATION DIVISION
Wichita, Kansas

I (did / did not) observe this plugging.
DATE OCT 23 1997

INV. NO. 49269

Signed Kevin D Strube
(TECHNICIAN)

10-10