

To: 1 090267 4-13  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-093-20,154-00-00  
C SW SE, SEC. 12, T. 21 S, R. 35 WXE  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6593  
Operator: Coastal Oil & Gas Corp.  
Name & Address: 9 Greenway Plaza, Room 2782  
Houston, TX 77046

Lease Name Odd Williams Well # 1-2  
County Kearny  
Well Total Depth 5060 164.45 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 601

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Coastal Oil & Gas Corp. License Number 6593  
Address 9 Greenway Plaza, Room 2782, Houston, KS 77046

Company to plug at: Hour: 1:10 p.m. Day: 13 Month: 4 Year: 19 93

Plugging proposal received from Don Herrera  
(company name) Coastal Oil & Gas Corp. (phone) 713-877-1400

Work: 4 1/2" at 4958' w/185 sx cement, PBTD 4948', Perfs at 4090-94', 4198-4235', 4852-4859'  
1st plug pump 25 sx cement through tubing from 4198-3940',  
2nd plug perforate casing at 1198' and pump in 175 sx cement,  
3rd plug hook onto backside and pump in 125 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 p.m. Day: 13 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement through tubing from 4198-3940',  
2nd plug pulled tubing out of hole. Perforated casing at 1198'. Pumped in 175 sx Class H  
cement.

3rd plug hooked onto backside and pumped in 125 sx Class H Cement.

Maximum pressure 350 psi and shut in 325 psi.

Remarks: Used Class H cement by Halliburton. No casing recovery.

I (did / did not) observe this plugging.  
If an additional description is necessary, use BACK of this report.

**INVOICED**  
DATE 4-22-93  
INV. NO. 37599  
4-13

APR 15 1993  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
Signed \_\_\_\_\_  
(TECHNICIAN)