

To: **1 090454**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-11

API NUMBER 15-093-20,648,0001

C SW _____, SEC. 11, T 21 S, R 38 X/

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Flintjer Well # 1

Operator: Beren Corporation

County Kearny

Name & Address P.O. Box 723

Well Total Depth 3228 104.91 to:

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Beren Corporation License Number 5364

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 2 p.m. Day: 11 Month: 8 Year: 1994

Plugging proposal received from George Jorgenson

(company name) Beren Corporation (phone) 913-628-6101

vers: 5 1/2" at 3228' w/700 sx cement, Perfs at 3179-97'

1st plug pump 3 sx hulls and fill casing with cement,

2nd plug pump 150 sx cement down 8 5/8" X 5 1/2".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:35 p.m. Day: 11 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 100 sx cement, gel to 920', and

100 sx cement to surface. Maximum pressure 500 psi and shut in 500 psi.

2nd plug hooked onto backside and pumped in 150 sx cement.

Maximum pressure 1000 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

AUG 29 1994

DATE _____

INV. NO. 41065

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1994
CONSERVATION DIVISION
WICHITA, KANSAS