

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-03306-00-00
Spot: SWSESW Sec/Twnshp/Rge: 16-15S-13W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: RUPPENTHAL Well #: 2
County: RUSSELL Total Vertical Depth: 3331 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3322		100 SX
SURF	8.625	152		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2017 3:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: LYLE L. GUNN Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2017 5:45 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Sanded off bottom and placed 5 sx cement on top. Perforated at 1450', 855' and 220'. Ran tubing to 1500' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 500' and pumped 50 sx cement. Circulated cement to pit. POOH. Hooked to braden head and pumped 20 sx cement pressured to 250 psi. Topped off casing with 20 sx cement. Casing stayed full.

GPS: 38.74147 -098.77577

Remarks: QUALITY CEMENTING TICKET # 064

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 13 2017

INVOICED
NOV - 9 2017