

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21863-00-01  
Spot: NESWNWNW Sec/Twnshp/Rge: 4-14S-31W  
834 feet from N Section Line, 356 feet from W Section Line  
Lease Name: HESS Well #: 1-4  
County: GOVE Total Vertical Depth: 4650 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4643		175 SX
SURF	8.625	220		165 SX
TI	2.875	4227		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2017 12:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING COMP Phone: (620) 617-3357

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement, 1400 # gel and 700 # hulls.  
8 5/8' surface casing set at 220' w/165 sx cement.  
5 1/2" production casing set at 4643' w/175 sx cement.  
TD 4650'. PBD 4634'.  
Perforations: 4185' - 4190' and 4218' - 4222'.  
Port Collar set at 2420' w/255 sx cement.  
Top Down Plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/10/2017 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 5 1/2' production casing and established injection rate of 4.5 BPM at 500 #.  
Pumped 80 sx cement w/400 # hulls followed by 1100 # gel mixed at 2 barrels per 100 # sx gel.  
Followed with 285 sx cement. Maximum pressure 500 psi. Connected to 8 5/8" surface casing  
and pumped 5 sx cement. Pressured to 300 psi.

GPS: 38.87115N -100.77846W

Perfs:

Top	Bot	Thru	Comments
4218	4222		
4185	4190		

Remarks: QES PUMPED SERVICES LLC TICKET # 53.621

Plugged through: CSG

District: 04

KCC WIC: \_\_\_\_\_ Signed Darrel Dipman  
(TECHNICIAN) CM

OCT 30 2017

RECEIVED

OCT 13 2017

INVOICED  
NOV - 9 2017