

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-05270-00-00
Spot: E2SENW Sec/Twnshp/Rge: 18-17S-1W
1980 feet from N Section Line, 2310 feet from W Section Line
Lease Name: EASON Well #: 2
County: MCPHERSON Total Vertical Depth: 2684 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2659		150 SX
SURF	7	2663		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2017 12:30 PM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: BRYAN HESS Company: HESS OIL CO Phone: (620) 241-4640

Proposed Plugging Method: AS PER KCC RULES & REGS. SET PLUG @ 2610' CAP WITH 4 SX CEMENT. 25 SX CEMENT @ 1100'. 250 FT CIRCULATE TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2017 12:30 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

SANDED OFF BOTTOM CAPPED WITH 25 SX COMMON CEMENT. RAN IN AND TAGGED @ 2750'. PERFORATED @ 1100' RAN IN 2 7/8" TUBING TO 1100' PUMPED 25 SX COMMON CEMENT. SURFACE @ 250' 65 SX AND CIRCUALTED TO SURFACE. TIED ON TO BACKSIDE PUMPED 150 SX CIRCUALTED TO SURFACE BETWEEN 10 3/4" AND 7" SURFACE PIPE.

Perfs:

Top	Bot	Thru	Comments
2665	2750		CSG
0	250		CSG

Remarks: COPELAND TICKET #C45933

Plugged through: CSG

District: 02

Signed Jerry Spurling
(TECHNICIAN)

INVOICED
NOV - 9 2017

18