

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-23495-00-01  
Spot: NWSENE Sec/Twnshp/Rge: 36-24S-10E  
4499 feet from S Section Line, 364 feet from E Section Line  
Lease Name: MOCK Well #: 15A  
County: GREENWOOD Total Vertical Depth: 1840 feet

Operator License No.: <u>4111</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>JOHN HENRY OIL LLC</u>	<u>PROD</u>	<u>2.875</u>	<u>1867</u>		<u>50 SX</u>
Address: <u>PO BOX 106</u>	<u>SURF</u>	<u>10.75</u>	<u>200</u>		<u>20 SX</u>
<u>EUREKA, KS 67045</u>	<u>SURF</u>		<u>203</u>		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2017 8:30 AM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Revd. from: JOHN MOCK Company: \_\_\_\_\_ Phone: (620) 583-3010

Proposed Plugging Method: Tree Limb, Heavy Rock, Small Rock, Cement

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/13/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

built rock bridge @ 1790', spotted 10 sxs cement w/dump baler, built rock bridge @ 900', spotted 10 sxs cement w/dump baler, ran tubing to 250', pumped 128 sxs cement to surface gel spacers between cement plugs.

Perfs:

RECEIVED  
KCC DIST # 3  
OCT 31 2017  
CHANUTE, KS

*MH*

INVOICED

NOV - 9 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

