

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19434-00-00
Spot: NESWSENV Sec/Twnshp/Rge: 5-35S-13E
3221 feet from S Section Line, 3534 feet from E Section Line
Lease Name: JR HYDER-STEINBERGER U Well #: 7
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 6 | 750 | | 0 SX |
| SURF | 8.5 | 40 | | 0 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 08/24/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" inside 2" to 660' gelled hole and spotted 20 sack plug. Pulled 1" and shot off 2" at 400'. Pulled 400' of 2". Perforated casing at 275'. Ran 1" back into 400' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 130 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 700 | 710 | | |

RECEIVED
KCC DIST # 3
OCT 17 2017
CHANUTE, KS
DS
INVOICED
NOV - 9 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY THE OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed D. Sims
(TECHNICIAN)