

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19428-00-00
Spot: SWSWSWNW Sec/Twnshp/Rge: 5-35S-13E
2847 feet from S Section Line, 5112 feet from E Section Line
Lease Name: J R HYDER-STEINBERGER U Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	750		0 SX
SURF	10	40		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 08/21/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 690' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 275'.
Ran 1" back into 275' and circulated cement to surface. Pulled 1" and topped well off. A total
of 125 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
700	710		

RECEIVED
KCC DIST # 3
OCT 17 2017
CHANUTE, KS
DS
INVOICED
NOV - 9 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)