

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-20783-00-00
Spot: SWSESW Sec/Twnshp/Rge: 20-18S-11W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HAMMEKE Well #: 1
County: BARTON Total Vertical Depth: 3441 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3441 | | 100 SX |
| SURF | 8.625 | 267 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2017 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRBY KRIER Company: KRIER, KIRBY OIL, INC. Phone: (620) 562-7637

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 670' and 250'. Ran tubing to 3100' and pumped 10 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1350' and pumped 45 sx cement w/100 # hulls. Pulled tubing to 670' and pumped 30 sx cement w/100 # hulls. Pulled tubing to 250'. Circulated cement to surface with 25 sx cement. Shut in casing. Circulated cement to surface on backside with 75 sx cement. Topped off with 5 sx cement.

GPS: 38.46481 -098.56712

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3330 | 3333 | | |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: T&E
ESG

INVOICED
NOV - 9 2017

District: 04

Signed

Bruce Rodie

KCC WICHITA

(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 19 2017

Form CP-2/3