

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-23265-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 32-33S-13E
566 feet from S Section Line, 2032 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 12
County: CHAUTAUQUA Total Vertical Depth: 1082 feet

Operator License No.: 33252
Op Name: MATADOR, INC.
Address: PO BOX 337
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1082		
SURF	7	40		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: TIM D. NORDELL Company: _____ Phone: (620) 725-3366

Proposed Plugging Method: RUN 1' TO TD, GEL HOLE. SPOT 5 SX CMT @ PERFS. PULL UP TO 700' SPOT 5 SX CMT. SHOOT OFF 4.5" @ 50'. RUN 1' BACK IN TO 275' CMT TO SURF.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/31/2017 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1000' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 39 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1004	1018		

RECEIVED
KCC DIST # 3
OCT 17 2017
CHANUTE, KS
DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST LETTER SENT TO OPERATOR BY THE KCC. OPERATOR HAD LOST LEASE ON PROPERTY.

Plugged through: TBG

District: 03

Signed D. Sims
(TECHNICIAN)

INVOICED
NOV - 9 2017