

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-22315-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 5-34S-13E  
3684 feet from S Section Line, 1670 feet from E Section Line  
Lease Name: A L KIRKPATRICK Well #: 8  
County: CHAUTAUQUA Total Vertical Depth: 1226 feet

Operator License No.: 33252  
Op Name: MATADOR, INC.  
Address: PO BOX 337  
SFDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1226		
SURF	7	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: TIM D. NORDELL Company: \_\_\_\_\_ Phone: (620) 725-3366

Proposed Plugging Method: RUN 1" TO TD, GEL HOLE, SPOT 5 SX CMT @ PERFS. PULL UP TO 700' SPOT 5 SX CMT. SHOOT OFF 4.5" @ 500'. PULL UP TO 275' CMT TO SURF.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 08/28/2017 12:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 1100' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled 1" out and shot casing at 275'. Tried to pull casing and couldn't get it to come out. Ran 1" back into 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well. Well was cut off and location restored.

**Perfs:**

Top	Bot	Thru	Comments
1014	1027		

RECEIVED  
KCC DIST # 3  
OCT 17 2017  
CHANUTE, KS  
DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST LETTER SENT TO OPERATOR BY THE KCC. OPERATOR HAD LOST LEASE ON PROPERTY.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)