

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita. KS 67202-1513

API Well Number: 15-019-21515-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 5-34S-13E  
4283 feet from S Section Line, 1691 feet from E Section Line  
Lease Name: KIRKPATRICK Well #: 4  
County: CHAUTAUQUA Total Vertical Depth: 1669 feet

Operator License No.: 33252  
Op Name: MATADOR, INC.  
Address: PO BOX 337  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1669		
SURF	7	40		

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/08/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: TIM D. NORDELL Company: Phone: (620) 725-3366

Proposed Plugging Method: RUN 1" TO TD, GEL HOLE, SPOT 5 SX CMT @ PERFS. PULL UP TO 700' SPOT 5 SX CMT. SHOOT OFF 4.5" @ 500'. PULL UP TO 275' CMT TO SURF.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/08/2017 12:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 1230' gelled hole and spotted 5 sack plug. Pulled up to 800' and spotted 5 sack plug. Pulled 1" out and shot casing off at 280'. Pulled casing. Ran 1" back into 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 78 sacks of cement were used to plug this well. Well was cut off and location restored.

**Perfs:**

Top	Bot	Thru	Comments
1283	1289		
RECEIVED KCC DIST # 3 OCT 17 2017 CHANUTE, KS DS INVOICED NOV - 9 2017			

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT TO OPERATOR BY THE KCC. OPERATOR HAD LOST LEASE ON PROPERTY.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)