

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21516-00-00

Spot: NENWNE

Sec/Twnshp/Rge: 5-34S-13E

4879 feet from S Section Line, 1720 feet from E Section Line

Lease Name: KIRKPATRICK

Well #: 3

County: CHAUTAUQUA

Total Vertical Depth: 1129 feet

Operator License No.: 33252

Op Name: MATADOR, INC.

Address: PO BOX 337
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1129		
SURF	7	40		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/29/2017 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Revd. from: TIM D. NORDELL

Company:

Phone: (620) 725-3366

Proposed Plugging Method: RUN 1" TO TD, GEL HOLE, SPOT 5 SX CMT @ PERFS. PULL UP TO 700' SPOT 5 SX CMT. SHOOT OFF 4.5" @ 600'. PULL UP TO 275' CMT TO SURF.

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed: 08/29/2017 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1100' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled 1" out and tried to shoot casing at 400'. Couldn't pull casing. Shot casing again at 275'. Still couldn't pull casing. Ran 1" back into 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 70 sacks of cement were used to plug this well. Well was cut off and location restored.

Top	Bot	Thru	Comments
1122	1128		

RECEIVED
KCC DIST # 3
OCT 17 2017
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST LETTER SENT TO OPERATOR BY THE KCC.
OPERATOR HAD LOST LEASE ON PROPERTY.

INVOICED

Plugged through: TBG

NOV - 9 2017

District: 03

Signed



(TECHNICIAN)