

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-00278-00-01
Spot: NENESE Sec/Twnshp/Rge: 7-9S-21W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: COOLEY Well #: 1
County: GRAHAM Total Vertical Depth: 2275 feet

Operator License No.: 3809
Op Name: MEM PARTNERSHIP LP, A GENERAL P
Address: PO BOX 130832
SPRING, TX 77393

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3795		125 SX
SURF	8.625	262		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2017 11:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: WILLIAM STORY Company: MEM PARTNERSHIP LP, A GENER Phone: (936) 828-6018

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Well was completed as a cedar hills swd with a 4 1/2" liner.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2017 12:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1232' and pumped 95 sx cement. Good circulation of cement. Pulled tubing out.
Topped off casing with 20 sx cement. Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3787	3790		

Remarks: HURRICANE TICKET # 100817

Plugged through: TBG

District: 04

Signed _____

(Signature)
(TECHNICIAN)

CM

OCT 23 2017

KCC WICHITA

OCT 23 2017

OCT 30 2017

RECEIVED

INVOICE
NOV - 9 2017