

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-23028-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 21-14S-22W
1330 feet from N Section Line, 700 feet from E Section Line
Lease Name: HONAS Well #: A2
County: TREGO Total Vertical Depth: 4225 feet

Operator License No.: 31528 String Size Depth (ft) Pulled (ft) Comments
Op Name: MIKE KELSO OIL, INC. PROD 5.5 4224 175sx
Address: PO BOX 467 SURF 8.625 253 170 SX
CHASE, KS 67524

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/18/2017 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL, INC. DBA Phone: (620) 938-2943

Proposed Plugging Method: Ordered 380 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 1692' w/320 sx cement.
Perforations: 3984' - 3986', 4053' - 4056', 4085' - 4092', 4096' - 4102', 4133' - 4140' and 4156' - 4158'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2017 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4170' and pumped 16 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 1750' and pumped 200 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 20 sx cement. Backside full of cement. Shut in pressure 150 psi.

GPS: 38.82539 -09976605

Perfs:


Top	Bot	Thru	Comments
4156	4158		
4133	4140		
4096	4102		
4085	4092		
4053	4056		
3984	3986		

Remarks: COPELAND ACID AND CEMENTING TICKET # 45781

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 19 2017

Form CP-2/3

INVOICED
NOV - 9 2017