

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-22082-00-00  
Spot: SENYSE Sec/Twnshp/Rge: 5-12S-14W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: RODA B Well #: 1  
County: RUSSELL Total Vertical Depth: 3362 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3361		150 SX
SURF	8.625	282		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2017 8:30 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: TODD L. DINKEL Company: G L M COMPANY Phone: (785) 639-5415

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/100 # hulls.  
Port Collar at 885' w/225 sx cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2017 1:00 PM KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Ran tubing to 2900' and pumped 50 sx cement. Pulled tubing to 2150' and pumped 50 sx cement. Pulled tubing to 1400' and pumped 100 sx cement. Circulated heavy mud and cement to pit. POOH. Hooked to casing and pumped 40 sx cement. Cement circulated out of the braden head.

GPS: 39.03521 -098.89615

**Perfs:**

Top	Bot	Thru	Comments
3050	3052		
3003	3005		

Remarks: GLOBAL CEMENTING TICKET # 308

Plugged through: TBG

District: 04

Signed

*Ray A Dinkel*

(TECHNICIAN)

CM

SEP 25 2017

KCC WICHITA

OCT 17 2017

RECEIVED

Form CP-2/3

INVOICE

NOV - 9 2017