

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-00616-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 32-5S-20W
2970 feet from S Section Line, 330 feet from W Section Line
Lease Name: RAY B Well #: 3
County: PHILLIPS Total Vertical Depth: 3630 feet

Operator License No.: 30606 String Size Depth (ft) Pulled (ft) Comments
Op Name: MURFIN DRILLING CO., INC. PROD 7 3609 100 SX
Address: 250 N WATER STE 300 SURF 10.75 165 125 SX
WICHITA, KS 67202

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/18/2017 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 75 sx common cement w/3% cc, 390 sx 60/40 pozmix 4% gel cement, 23 sx gel (100 # bags) 800 # hulls.
Squeezed at 05' - 2659' w/150 sx cement.
Open Hole: 3609' - 3630'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2017 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1740' and 1150'. Ran tubing to 3593' and pumped 23 sx gel followed by 75 sx common cement w/3% cc and 300 # hulls. Pulled tubing to 1735' and pumped 315 sx cement to circulate cement to surface. Pulled all tubing. Topped off 7" casing with 25 sx cement. Hooked to 10 3/4" x7" annulus and pumped 50 sx cement at 150 psi.

GPS: 39.57564N -099.60799W

Perfs:

Top	Bot	Thru	Comments
3609	3630		

Remarks: HURRICANE SERVICES INC. TICKET # 100815

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

OCT 30 2017

RECEIVED

OCT 19 2017

INVOICED

NOV - 9 2017