

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24345-00-00
Spot: E2W2SENE Sec/Twnshp/Rge: 12-6S-20W
1980 feet from N Section Line, 730 feet from E Section Line
Lease Name: GARTRELL Well #: 1-12
County: ROOKS Total Vertical Depth: 3688 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3685		325 SX
SURF	8.625	218		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2017 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 15 sx gel (100 # bags) and 200 # hulls.
DV Tool at 1724' w/200 sx cement. TOC at 290'.
Squeezed at 3600' - 3602' w/cement retainer at 3646
Production Perforations: 3588' - 3590'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2017 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated 2 holes at 205'. Ran tubing to 3559' and pumped 15 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1710' and pumped 170 sx cement to circulate cement to surface. Closed backside valve. Pumped 10 sx cement to circulate 8 5/8" x 5 1/2" annulus to surface. Pulled all tubing and topped off 5 1/2" casing with 20 sx cement.

GPS: 39.54776N -099.49290W

Perfs:

Top	Bot	Thru	Comments
3588	3590		

Remarks: HURRICANE SERVICES INC. TICKET # 100810

Plugged through: TBG

INVOICE
NOV - 9 2017

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

OCT 17 2017

RECEIVED

SEP 29 2017