

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-22245-00-00
Spot: N2NESENE Sec/Twnshp/Rge: 23-30S-7W
1575 feet from N Section Line, 330 feet from E Section Line
Lease Name: HUFFORD Well #: 3
County: KINGMAN Total Vertical Depth: 4266 feet

Operator License No.: 6236
Op Name: MTM PETROLEUM, INC.
Address: 2370 SOUTH STATE ROAD 14 PO BOX
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3850		
PROD	4.5	4260		170 SX
SURF	8.625	223		150 SX
T1	2.342	4200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 955-6014

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2017 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

LAY DOWN RODS & TUBING FROM WELL. SET CIBP @ 3720' & CAPPED WITH 2 SKS CEMENT. RECOVERED 4 1/2" CASING FROM 2715' & PULLED CASING TO 1150' SPOTTED 35 SXS CEMENT. TAG 800'. PULLED CASING TO 750' & SPOTTED 35 SX CEMENT. PULLED CASING TO 270' & CIRCULATED CEMENT TO SURFACE WITH 120 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4166	4178		

Remarks: QUALITY WELL SERVICE COMMON CEMENT 3% CACL.

Plugged through: CSG

District: 02

Signed _____


(TECHNICIAN)

INVOICE
NOV - 9 2017