

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21514-00-00
Spot: NWSENE Sec/Twnshp/Rge: 5-33S-8W
720 feet from N Section Line, 500 feet from E Section Line
Lease Name: STUART Well #: 1
County: HARPER Total Vertical Depth: 4587 feet

Operator License No.: 6236
Op Name: MTM PETROLEUM, INC.
Address: 2370 SOUTH STATE ROAD 14 PO BOX
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>PKR</u>		<u>417</u>		
<u>PROD</u>	<u>4.5</u>	<u>4577</u>		<u>100 SX</u>
<u>SURF</u>	<u>8.625</u>	<u>233</u>		<u>175 SX</u>
<u>T1</u>	<u>2.375</u>	<u>4416</u>		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/23/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 955-6014

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIBSON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2017 4:30 PM KCC Agent: STEVE VANGIBSON

Actual Plugging Report:

PULLED AND LAYED OUT RODS & TUBING FROM WELL. RIGGED UP & SET A CIBP AT 4450'. THE BP WAS CAPPED WITH 2 SKS CEMENT. CUT CASING AT 3225' & LAYED OUT TO 1350' WHERE 35 SX OF CEMENT WAS SPOTTED. PULLED CASING TO 850' WHERE 35 SX OF CEMENT WAS SPOTTED. PULL CASING TO 360' & CIRCULATED CEMENT TO SURFACE WITH 150 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
<u>4493</u>	<u>4496</u>		

Remarks: QUALITY WELL SERVICE COMMON CEMENT

INVOICE

NOV - 9 2017

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)