

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-22312-00-00  
Spot: SESWNWSW Sec/Twnshp/Rge: 29-28S-8W  
1325 feet from S Section Line, 642 feet from W Section Line  
Lease Name: BOCK Well #: 1-29  
County: KINGMAN Total Vertical Depth: 4564 feet

Operator License No.: 34848  
Op Name: POLLOK ENERGY, LLC  
Address: 501 N. 4TH PO BOX 106  
PURCELL, OK 73080

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2017 8:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: RENE Company: DUKE DRILLING Phone: (620) 253-6588

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE  
Date/Time Plugging Completed: 10/28/2017 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

RAN DRILL PIPE OPEN END TO 1250' SPOTTED 35 SX CEMENT. PULLED DRILL PIPE TO 850' SPOTTED 35 SX CEMENT. PULL DRILL PIPE TO 270' SPOTTED 35 SX CEMENT. PULLED DRILL PIPE TO 60' SPOTTED 25 SX CEMENT. PULL DRILL PIPE & TOPPED OFF CEMENT. CIRCULATED 30 SX CEMENT IN RAT HOLE & 20 SX IN MOUSE HOLE.

Remarks: BASIC CEMENT 60/40 4% GEL

Plugged through: DP

INVOICED  
NOV - 9 2017

District: 02

Signed [Signature] DISTRICT SUPERVISOR  
(TECHNICIAN)