

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01309-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 13-24S-12E
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: GEIST Well #: 8
County: GREENWOOD Total Vertical Depth: 1600 feet

Operator License No.: <u>5394</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>ABDERHALDEN, R. R.</u>	PROD	5.5	1809		100 SX
Address: <u>100 S. MAIN, STE 510</u> <u>WICHITA, KS 67202</u>	SURF	8.63	122		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2017 12:00 PM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Revd. from: DWAIN G. STOUT Company: _____ Phone: (316) 640-9089

Proposed Plugging Method: Shoot off casing @1000 ft. Pull casing. Run tubing to 1000 ft. and set a 50 ft. cement plug. Pull tubing to 800 ft and set a 50 ft. cement plug. Pull tubing to 250 ft. and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 10/17/2017 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

junk pipe in well bore 1100' unable to retrieve, shot casing off @ 1000', pulled casing out, ran tubing to 800', pumped 20 sxs cement, pulled tubing to 250', pumped 85 sxs cement to surface, gel spacer between cement plug.

RECEIVED
KCC DIST # 3
OCT 24 2017
CHANUTE, KS

MH


INVOICED
10/17 - 2 2017

Remarks:

Plugged through: TBG

District: 03

Signed: Mike Heffern
(TECHNICIAN)



Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
10-18-11	11046	Giest H 8				G.W.	Ks
Customer R.R.A. Inc. Mailing Address 100 S. MAIN ST STE 510 City Wichita State Ks Zip Code 67202			Safety Meeting	Unit #	Driver	Unit #	Driver
				102	RICK		
				113	ALAN - M		
				141	AB		

Remarks: Safety Meeting Plug Down 2 3/8 Tubing w/ 5 1/2 casing pulled

20 SK's @ 800'

85 SK's 150' to Surface.

105 SK's TOTAL

Pull Tubing TOP OF well w/ cement

Get Spacers Between Plug's

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.