

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23608-00-00  
Spot: SENWSWNW Sec/Twnshp/Rge: 20-7S-20W  
1690 feet from N Section Line, 610 feet from W Section Line  
Lease Name: LABARGE Well #: 3-20  
County: ROOKS Total Vertical Depth: 3601 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3598		240 SX
SURF	8.625	209		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2017 10:30 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.  
Port Collar at 1666' to surface with 190 sx cement.  
Production perforations: 3234' - 3402'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2017 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2' casing and pumped 50 sx cement w/200 # hulls followed by 14 sx gel, then pumped 175 sx cement. Shut in pressure 500 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 600 psi.

GPS: 39.43296N -099.58225W

Perfs:

Top	Bot	Thru	Comments
3399	3402		
3357	3360		
3306	3308		
3234	3237		

INVOICED  
NOV - 3 2017

Remarks: GLOBAL CEMENTING TICKET # 3091

Plugged through: CSG

District: 04

Signed

Pat Bedore

KCC WICHITA

(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 24 2017

Form CP-2/3