

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23598-00-00
Spot: SWSWNESW Sec/Twnshp/Rge: 20-7S-20W
1420 feet from S Section Line, 1330 feet from W Section Line
Lease Name: LABARGE Well #: 1-20
County: ROOKS Total Vertical Depth: 3565 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3564 | | 240 SX |
| SURF | 8.625 | 208 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2017 8:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 14 sx gel (100 # bags) and 500 # hulls.
Port Collar at 1634' to surface with 200 sx cement.
Production perforations: 3254' - 3312'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2017 10:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls followed by 14 sx gel, then pumped 150 sx cement. Shut in pressure 1100 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Annulus standing full.

GPS: 39.42697N -099.57967W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3308 | 3312 | | |
| 3254 | 3258 | | |

Remarks: GLOBAL CEMENTING TICKET # 3090

Plugged through: CSG

INVOICED

10/21 - 8 2017

District: 04

Signed _____
KCC WICHITA

Pat Bedore
(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 24 2017