

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20515-00-00
Spot: N2SWNWSE Sec/Twnshp/Rge: 24-4S-21W
1900 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GARLETTS Well #: 1-24
County: NORTON Total Vertical Depth: 3625 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3624 | | 395 SX |
| SURF | 8.625 | 207 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2017 8:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 13 sx gel and 300 # hulls.
PC at 1768'
Production perforations: 3341' - 3392'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2017 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2' casing and pumped 50 sx cement w/150 # hulls followed by 11 sx gel, then pumped 190 sx cement. Shut in pressure 1100 psi. Hooked to 8 5/8' x 5 1/2' annulus and pumped 10 sx cement. Backside standing full.

GPS: 39.68841N -099.63636W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3389 | 3392 | | |
| 3373 | 3376 | | |
| 3341 | 3343 | | |

Remarks: GLOBAL CEMENTING TICKET #3089

Plugged through: CSG

INVOICED
NOV - 8 2017

District: 04

Signed _____

Pat Bedore

KCC WICHITA

(TECHNICIAN)

CM

OCT 30 2017

Form CP-2/3

OCT 19 2017

RECEIVED