

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20612-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 25-3S-22W
2145 feet from S Section Line, 480 feet from W Section Line
Lease Name: JACOBSON Well #: 1-25
County: NORTON Total Vertical Depth: 3993 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3917		490 SX
SURF	8.625	259		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2017 8:30 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 310 sx 60/40 pozmix 4% gel cement, 1400 # gel and 300 # hulls.
8 5/8" surface casing set at 259' w/160 sx cement.
5 1/2' production casing set at 3917' w/265 sx cement.
Port Collar set at 2030' w/225 sx cement.
TD 3993'.
Perforations: 3662' - 3668', 3805' - 3812' and 3852' - 3859'.
Top Down Plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2017 10:20 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 5 1/2' production casing and pumped 60 sx cement w/300 # hulls followed by 1400 # gel and 160 sx cement. Pressured to 1000 psi. Cement 0' to 1688'. Anhydrite 2031' - 2060'. Connected to 8 5/8" surface casing with immediate pressure to 300 psi.

GPS: 39.76153N -09975681W

Perfs:

Top	Bot	Thru	Comments
3852	3859		
3805	3812		
3662	3668		

INVOICED
10/11 - 3 2017

Remarks: GLOBAL OILFIELD SERVICES TICKET # 3110

Plugged through: CSG

District: 04

KCC WICHITA

Signed

Darrel Dipman

(TECHNICIAN)

CM

OCT 30 2017

RECEIVED

OCT 13 2017